

# FEMA Projects Slide Repair Specifications

## Round one of projects – February 2020

### Savoy Clear Creek Road Slide Repair Specs

#### Site #1

GPS – 36.72699, -84.15298

205 total Linear Feet repair

205 LF – 20 FT drilled or launched soil nails

2050 SQFT – 8in Shotcrete

400 LF - Horizontal Drains

#### Site #2

GPS – 36.72753, -84.15176

159 total Linear Feet repair

159 LF – 20 FT drilled or launched soil nails

1590 SQFT – 8in Shotcrete

300 LF – Horizontal Drains

### Little Wolf Creek Road Slide Repair Specs

209 total Linear Feet repair

140 LF – 20 FT drilled or launched soil nails

69 LF – 30 FT drilled or launched soil nails

2090 SQFT – 8in Shotcrete

70 CY – Lightweight backfill

400 LF – Horizontal Drains